STATE of NEW HAMPSHIRE
DEPARTMENT of ADMINISTRATIVE SERVICES
DIVISION of PUBLIC WORKS - DESIGN & CONSTRUCTION
POB 483, 7 Hazen Drive – Room 250
Concord, New Hampshire 03302-0483
Phone 603-271-3516, Fax 603-271-3515

CHARLES M. ARLINGHAUS
Commissioner

ADDENDUM NUMBER 04

FOR

ARPA- CAMPGROUND EXPANSION PROJECTS

A FEDERAL AID PROJECT

PAWTUCKAWAY STATE PARK

TOILET BUILDING RENOVATIONS

PARK OFFICE - 7 PAWTUCKAWAY ROAD,

NOTTINGHAM, NH 03590

DIVISION OF PUBLIC WORKS PROJECT NUMBER 81205R

CONTRACT B

DEPARTMENT OF NATURAL AND CULTURAL RESOURCES

MAY 6, 2024

DOCUMENT 00914

ADDENDUM NUMBER 04

TO: ALL CONTRACT BIDDERS OF RECORD

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated April 4, 2024, addendum number 1 dated April 17 ,2024, addendum number 2 dated April 29 ,2024 and addendum number 3 dated May 1 ,2024 with amendments and additions noted below.
Acknowledge receipt of this Addendum in the space provided in the Proposal Form. Failure to do so may disqualify the Bidder.

This Addendum consists of 2 pages.

CHANGES TO INTERGRATED PROJECT DEVELOPMENT (IPD WEB) BIDDING FORM

1. Technical issues with bid item 903 have been resolved.
2. Add bid item number 904 for item listed below.

CHANGES TO THE SPECIFICATIONS

DOCUMENT 01200 – PRICE AND PAYMENT PROCEDURES

3. Add Part 1.8. F, Unit Prices Schedule. Items with the following paragraph:

   2. Item: Carry a cost of underground electrical service from existing meter kiosk between Bathhouse 5 & 6. This includes but not limited to: electrical trenching, bedding, backfilling, 4" PVC conduit, PVC sweeps, with pull string for final connection from remote meter to bathhouse 5 and 6 by the electrical contractor. Estimate distance from Bathhouse 5 to remote meter is approximately 175 LF and estimate distance from Bathhouse 6 to remote meter is approximately 275 LF for a total of 450 LF of underground electrical service.

Michelle L. Juliano

Michelle Juliano, P.E., Assistant Director
Division of Public Works Design and Construction

END OF DOCUMENT