

**SPECIAL ATTENTION****THIS PROJECT IS TO BE BID AND CONSTRUCTED UNDER THE  
2016 STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION****NOTICE OF SUPPLEMENTAL SPECIFICATIONS**

The following table is a list of all of the Supplemental Specifications that have been adopted as additions or revisions to the *Standard Specifications for Road and Bridge Construction, March 2016* Edition as of the date of this Proposal. The Bidder is responsible to examine each item to determine its effect, if any, upon the Contract.

**Note:** Due to the limited scope of some projects, not all Supplemental Specifications will be included in all Proposals. All Supplemental Specifications are available on-line: [www.nh.gov/dot/org/projectdevelopment/highwaydesign/specifications/](http://www.nh.gov/dot/org/projectdevelopment/highwaydesign/specifications/).

| Section                    | Description                                       | Revision  | Previous Revision Date | Current Revision Date |
|----------------------------|---|---|------------------------|-----------------------|
| <b><i>DIVISION 100</i></b> |   |   |                        |                       |
| 101                        | Definitions and Terms                             | 101.79 – Revises Frequency of QPL Updates (06/06/17)<br>101.116-119 – Revises Definitions of Weather Days and Working Days (04/02/18) | 06/06/17               | 04/02/18              |
| 105.02                     | Plans and Working Drawings                        | Section Rewrite-Approval/Acceptance/Documentation<br><small>(NHDOT: 12/07/23; FHWA: 11/16/23)</small>                                 | -                      | 12/04/23              |
| 106.04                     | Qualified Products List                           | Revises Frequency of Updates  |                        | 06/06/17              |
| 107.01                     | Legal Relations and Responsibility to Public      | 107.01 – Revises References to DES Rules and Regulations  |                        | 07/06/18              |
| 108.09                     | Prosecution and Progress                          | 108.09 – Amends the Requirements for Liquidated Damages   |                        | 07/06/18              |
| 109.04                     | Differing Site Conditions, Changes and Extra Work | Revises Rental Rate Blue Book Online Requirements (04/02/18)  | 01/06/12               | 04/02/18              |
| <b><i>DIVISION 200</i></b> |   |   |                        |                       |
| 211.3.4                    | Vibration Monitoring                              | Adds reference to pre- and post-construction survey requirements  |                        | 04/05/17              |
| <b><i>DIVISION 300</i></b> |   |   |                        |                       |

***DIVISION 400***

|     |                                  |   |          |          |
|-----|----------------------------------|---|----------|----------|
| 401 | Plant Mix Pavements -<br>General | <p>2.2.3 – Requires Suppliers to participate in NTPEP Asphalt Binder Suppliers (ABS) program (12/15/23)<br/><small>(NHDOT: 03/02/22; FHWA 12/15/23)</small></p> <p>3.9 – Asphalt Release Agents must be listed on QPL (12/15/23)<br/><small>(NHDOT: 03/02/22; FHWA 12/15/23)</small></p> <hr/> <p>Complete reorganization of Section 401, including incorporating all supplemental specifications thus far (01/28/21) <small>(NHDOT: 12/02/20/FHWA: 01/28/21)</small></p> <hr/> <p>2.5.1 - Adds winter binder to the design control points (04/05/17)</p> <p>2.10 – No greater than 1% TRB (06/06/17)</p> <p>3.4.1 – Revises Cold Feeder Requirements (07/06/18)</p> <p>3.4.7.1 – Revises Recycled Materials Weighing Procedures (07/06/18)</p> <p>3.4.11 - 3.4.15 – Describes Introduction of Recycled Materials at a Batch Plant and Controls Minimum Dry Time for Recycled Aggregates (07/06/18)</p> <p>3.5.2 &amp; 3.5.2.1 – Revises Recycled Materials Requirements (07/06/18)</p> <p>3.10.10.1 – Removes penalty for failing tack (06/06/17)</p> <p>3.12 – Allows a reduction in use of pneumatic-tired rollers (06/06/17)</p> <p>3.17.1.3 - Revise NETTCP QA Technologist requirements (11/07/18)</p> <p>3.17.3.1.1 – Revises HMA gradation specification limits, completes addition of winter binder, removes allowance for Aim change after two sub-lots (06/06/17)</p> <p>4.1.1 – Removes reference to Night Items (06/06/17)</p> | 01/28/21 | 12/15/23 |
| 403 | Pavement Item Numbers            | <p>403.1.3, 403.5.1.1 &amp; Item Key - Removes all references to Night Items and removes “percent wear” items. (06/06/17)</p> <p>403 Item Key - Total overhaul of Item Numbers and Descriptions to allow for type of mix in item description (07/27/20)</p>   | 07/27/20 | 07/01/21 |

|                            |                                    |  |          |          |
|----------------------------|------------------------------------|--|----------|----------|
|                            |                                    | 403 Item Key & 5.2 - Further Update of Item Descriptions to allow for type of mix (07/01/21)<br>(NHDOT: 12/02/20/FHWA: 01/28/21)   |          |          |
| 410                        | Bituminous Surface Treatment       | 2.1- Adopts new AASHTO Specifications for Emulsions (04/13/16)<br>3.4.1.1 – Revises pavement conditions, application rate for tack (01/04/17)<br>2.1.1, 2.1.2, 3.2, 3.3, 3.4 – Identifies tack sampling and penalties for non-conformance (06/06/17)<br>3.2 & 3.5.2 – Amends Distribution Equipment and Initiates an Annual Tack Truck Inspection Program (07/06/18) | 06/06/17 | 07/06/18 |
| 411                        | Pneumatic Tired Roller/Remove “AC” | 2.1.2/3.4.7 – Update language to remove references to “AC” and ¾” PMST (01/11/24)<br>3.5.5 – Requires the use of pneumatic tired rollers on all Section 411 paving (06/06/17).<br>5.1.1 – Ensures Tack Used for PMST and Leveling Course is a Pay Item (07/06/18)<br>Update Pay Item Description (Remove “AC”) 01/11/24<br>Removes Pay Items (04/02/18 & 01/11/24)   | 07/06/18 | 01/11/24 |
| 417                        | Rumble Strip Inlay                 | 2.1 & 3.7 – Specifies PMST as the asphalt inlay to fill in rumble strips   |          | 04/02/18 |
| <b><i>DIVISION 500</i></b> |                                    |  |          |          |
| 520                        | Portland Cement Concrete           | 3.8.1.1 – Revises the acceptable concrete delivery temp to 90° F (04/02/18)<br>3.1.6.2.1.2 A - Revise NETTCP QA Technologist requirements (11/07/18)   | 04/02/18 | 11/07/18 |
| 530                        | Waterproofing Concrete Surfaces    | Deletes Section 530  |          | 05/21/18 |
| 538                        | Barrier Membrane                   | 3.3.5 – Updates the laydown temperature range.   |          | 09/15/16 |
| 550                        | Structural Steel-Shim Plates       | 3.15.5.5 – Eliminate the use of weathering steel as a bearing shim plate (NHDOT: 01/08/20/FHWA: 03/18/20)  |          | 01/28/21 |

|                            |                                 |   |          |          |
|----------------------------|---------------------------------|---|----------|----------|
| 563                        | Bridge Fence                    | 2.8 – Allows aluminum ties for attaching bridge fence   |          | 09/15/16 |
| 568                        | Structural Timber               | 2.2, 3.4.4 & 3.4.5 – Adds specific references to AWWA Standards & wooden piles  |          | 04/02/18 |
| 582                        | Preformed Joint Filler          | 2.4 – Revises Preformed Joint Filler Requirements   |          | 04/02/18 |
| <b><i>DIVISION 600</i></b> |                                 |   |          |          |
| 603                        | Plastic Pipe                    | 2.3, 2.6 & 2.7 – Updated to include Polypropylene Pipe as well as associated UV Requirements (04/13/16)<br>2.13 – Adds Contractor's Option (06/02/16)   | 04/13/16 | 06/02/16 |
| 605                        | Plastic Pipe                    | 2.1 & 2.2 – Updated to include Polypropylene Pipe   |          | 04/13/16 |
| 606                        | Guardrail                       | 2.2 – Adds specific references to AWWA Standards & wooden piles   |          | 04/02/18 |
| 608                        | Detectable Warning Devices      | 2.6 – Updates Detectable Warning Device Requirements  |          | 04/02/18 |
| 609                        | Curbs                           | 2.4.1.1 – Allows the substitution of PG 76-28 binder in lieu of fibers  |          | 04/02/18 |
| 615                        | Cofferdam for Sign Installation | 5.1.5 – Revises payment for sheeting and shoring for sign structures  |          | 04/02/18 |
| 645                        | Erosion Control                 | 1.1 – Matting Section Revised and Pay Items Revised (04/02/18)<br>1.1 – 'Stabilization' changed to 'matting' (02/01/17)<br>Incorporates BFM, FRM and SMM into the Standard Specs (07/06/18)<br>1.2.1 – Add Erosion Control Plans to furnish for SWPPP (11/07/18)<br>3.1.5 – Update construction dates for allowable area of exposed, unstabilized soil (11/07/18) | 07/06/18 | 11/07/18 |
| <b><i>DIVISION 700</i></b> |                                 |   |          |          |
| 702                        | Bituminous Materials            | Amends/Corrects Table 702-1 & 702-2 (04/13/16 & 01/11/24)<br>Amends Tables, and Adds Test Method (05/11/16)   | 05/11/16 | 01/11/24 |