



# Information Report

SOMERSWORTH-ROCHESTER/BARRINGTON-ROCHESTER

43927

X-A005(541)

County: STRAFFORD  
 Date Bids Open: 12/5/2024  
 Scope of Work: Pavement preservation project to keep the sections of roadway in pavement preservation mode.  
 Location: NH 125 & Old Rochester Rd/Old Dover Rd  
 Completion Date: 9/26/2025  
 Proposal Guarantee: 5% of bid amount

Item Number	Item Description	Unit	Estimated Quantity
<b>SOMERSWORTH-ROCHESTER/BARRINGTON-ROCHESTER</b>			
<b>43927</b>			
<b>24604__ - Barrington-Rochester - NH 125</b>			
202.7	REMOVAL OF GUARDRAIL	LF	6,525.00
203.5561	EAGRT PLATFORM PREFERRED	U	19.00
206.1	COMMON STRUCTURE EXCAVATION	CY	26.00
304.301	CRUSHED GRAVEL	CY	13.00
304.32	CRUSHED GRAVEL FOR SHOULDER LEVELING	TON	710.50
403.11022	HBP-3/4" BINDER MIX, MACHINE METHOD, QC/QA TIER 2	TON	4,351.00
403.11942	HBP-1/2" SURFACE MIX, MACHINE METHOD, HIGH STRENGTH, QC/QA TIER 2	TON	12,681.00
403.11952	HBP-3/8" SURFACE MIX, MACHINE METHOD, HIGH STRENGTH, QC/QA TIER 2	TON	83.00
403.12	HBP-HAND METHOD	TON	280.00
403.16	PAVEMENT JOINT ADHESIVE	LF	130,838.00
403.4	MATERIAL TRANSFER VEHICLE (MTV)	TON	17,246.00
410.22	ASPHALT EMULSION FOR TACK COAT	GAL	6,660.00
411.1	HOT BITUMINOUS CONCRETE LEVELING COURSE	TON	215.00
417.	COLD PLANING BITUMINOUS SURFACES	SY	41,772.00

417.1181	COLD PLANING BITUMINOUS SURFACES, 18" WIDE X 1" DEEP	LF	4,515.00
417.412	RUMBLE STRIPS, 12" WIDE	LF	9,119.00
417.4122	RUMBLE STRIPS, 12" WIDE (SINUSOIDAL)	LF	2,184.00
417.53	REMOVE AND INLAY EXISTING RUMBLE STRIPS	LF	11,303.00
559.41	ASPHALTIC PLUG FOR CRACK CONTROL (F)	LF	85.00
604.0007	POLYETHYLENE LINER	EA	45.00
604.4	RECONSTRUCTING/ADJUSTING CATCH BASIN & DROP INLET	LF	45.00
604.52	RECONSTRUCTING/ADJUSTING DRAINAGE MANHOLES	LF	2.00
606.1254	BEAM GUARDRAIL (TERMINAL UNIT TYPE EAGRT, TL 3) (STEEL POST)	U	19.00
606.18001	31" W-BEAM GUARDRAIL WITH 8" OFFSET BLOCK (STEEL POST)	LF	5,400.00
608.1201	2" BITUMINOUS SIDEWALK	SY	11.80
608.2401	4" CONCRETE SIDEWALK	SY	105.00
608.54	DETECTABLE WARNING DEVICES, CAST IRON	SY	11.40
609.5	RESET GRANITE CURB	LF	145.00
609.811	BITUMINOUS CURB, TYPE B (4" REVEAL)	LF	3,686.00
615.0301	TRAFFIC SIGN TYPE C	SF	380.83
615.033	REMOVING TRAFFIC SIGN, TYPE C	U	42.00
615.0401	TRAFFIC SIGN TYPE AA	SF	175.50
615.043	REMOVING TRAFFIC SIGN TYPE AA	U	4.00
615.0501	TRAFFIC SIGN TYPE BB	SF	246.17
615.053	REMOVING TRAFFIC SIGN TYPE BB	U	10.00
615.0601	TRAFFIC SIGN TYPE CC	SF	209.40
615.063	REMOVING TRAFFIC SIGN TYPE CC	U	15.34
616.606	TRAFFIC SIGNAL DETECTOR LOOP 6 FT X 6 FT	EA	10.00
616.650	TRAFFIC SIGNAL DETECTOR LOOP 6 FT X 50 FT	EA	41.00
617.30101	SHORT-TERM COUNT STATION	EA	1.00
617.30102	SHORT-TERM COUNT STATION	EA	1.00

618.61	UNIFORMED OFFICERS WITH VEHICLE	\$	90,000.00
618.7	FLAGGERS	HR	1,800.00
621.2	RETROREFLECTIVE BEAM GUARDRAIL DELINEATOR	EA	81.00
621.31	SINGLE DELINEATOR WITH POST	EA	50.00
621.32	DOUBLE DELINEATOR WITH POST	EA	10.00
628.2	SAWED BITUMINOUS PAVEMENT	LF	352.00
632.1104	PREFORMED RETROREFLECTIVE TAPE, TYPE I (REMOVABLE) 4" LINE	LF	11,712.00
632.1118	PREFORMED RETROREFLECTIVE TAPE, TYPE I (REMOVABLE) 18" LINE	LF	342.00
632.5106	PREFORMED RETROREFLECTIVE TAPE, LEVEL I, 6" LINE	LF	638.00
632.5118	PREFORMED RETROREFLECTIVE TAPE, LEVEL I, 18" LINE	LF	342.00
632.52	PREFORMED RETROREFLECTIVE TAPE, LEVEL I, SYMBOL OR WORD	SF	1,675.00
632.7104	RETROREFLECTIVE POLYUREA PAVEMENT MARKING, 4" LINE	LF	120,496.00
632.7108	RETROREFLECTIVE POLYUREA PAVEMENT MARKING, 8" LINE	LF	331.00
632.911	OBLITERATE PAVE. MARKING LINE, 12" WIDE & UNDER	LF	4,725.00
632.92	OBLITERATE PAVEMENT MARKING, SYMBOL OR WORD	SF	1,533.00
645.512	COMPOST SOCK FOR PERIMETER BERM	LF	2,035.00
645.531	SILT FENCE	LF	2,035.00
645.611	BONDED FIBER MATRIX (BFM)	LB	1,857.00
646.21	TURF ESTABLISHMENT WITHOUT MULCH	SY	3,000.00
646.41	TURF ESTABLISHMENT WITH MULCH, TACKIFIERS AND HUMUS	SY	200.00
1010.15	FUEL ADJUSTMENT	\$	35,900.00
1010.2	ASPHALT CEMENT ADJUSTMENT	\$	50,000.00
1010.3	QUALITY CONTROL QUALITY ASSURANCE (QC/QA) ASPHALT	\$	84,498.00
<b>Incidentals</b>			
206.19	COMMON STRUCTURE EXCAVATION EXPLORATORY	CY	10.00
619.1	MAINTENANCE OF TRAFFIC	U	1.00
619.25	PORTABLE CHANGEABLE MESSAGE SIGN	U	6.00

692.	MOBILIZATION	U	1.00
699.	MISCELLANEOUS TEMPORARY EROSION AND SEDIMENT CONTROL	\$	5,000.00
1008.251	ALTERATIONS AND ADDITIONS AS NEEDED - TEMPORARY PEDESTRIAN ACCOMMODATIONS	\$	12,000.00
1010.15	FUEL ADJUSTMENT	\$	4,100.00