

The State of New Hampshire

Department of Environmental Services



Robert R. Scott, Commissioner

AMENDED WETLANDS AND NON-SITE SPECIFIC PERMIT 2023-02842

NOTE CONDITIONS

PERMITTEE: NH DEPT OF TRANSPORTATION

7 HAZEN DR

CONCORD NH 03301

PROJECT LOCATION: NH RT 121/CHESTER ROAD, AUBURN

Tax Map/Block/Lot(s): 23/no block/ROW

WATERBODY: MASSABESIC LAKE

AMENDMENT DATE: APRIL 24, 2024

ORIGINAL APPROVAL DATE: DECEMBER 11, 2023 EXPIRATION DATE: DECEMBER 11, 2028

Based upon review of permit application 2023-02842 in accordance with RSA 482-A and RSA 485-A:17, the New Hampshire Department of Environmental Services (NHDES) hereby issues this Wetlands and Non-Site Specific Permit. To validate this Permit, signatures of the Permittee and the Principal Contractor are required.

AMENDED PERMIT DESCRIPTION:

Amend Permit to: Dredge and fill a total of 3,266 square feet/278 linear feet of riverine, scrub-shrub palustrine and lacustrine wetlands to replace a 41-foot long x 5-foot diameter corrugated metal pipe culvert carrying an unnamed stream under NH Route 121 (Chester Road) approximately 600-feet north of Bunker Hill Road in the Town of Auburn, NH. The proposed project will install a 9-foot x 6.5 foot x 45-foot 4-sided box culvert with 2-foot embedment with concrete wingwalls upstream and downstream and a 3-foot diameter RCP culvert set 28-feet off the proposed box culvert. Impacts include grading along slope embankments (NHDOT 44167).

THIS PERMIT IS SUBJECT TO THE FOLLOWING AMENDED PROJECT-SPECIFIC CONDITIONS:

- 1. In accordance with Env-Wt 307.16, all work shall be done in accordance with the sequence and revised plans for State of New Hampshire Department of Transportation, NH Route 121 Culvert Replacement Wetlands Plans, Auburn, NH Project No 44167 (X-A00(339), dated February 2024 received by NHDES with the permit amendment request dated April 3, 2024.
- 2. In accordance with Env-Wt 527.05(a) In addition to complying with all applicable conditions in Env-Wt 307, the permit shall be contingent on review and approval by the department of final stream diversion that detail the timing and method of stream flow diversion during construction and show temporary siltation, erosion, and turbidity control measures to be implemented.
- 3. In accordance with Env-Wt 314.03, (a) The permittee shall notify the department in writing at least one week prior to commencing any work under the permit.
- 4. Wetland grading areas and vegetation clearing associated with proposed channel (at 3-foot diameter RCP inlet and outlet) and temporary water diversion structures shall be minimized to all extents possible during construction.
- 5. No person undertaking any activity shall cause or contribute to, or allow the activity to cause or contribute to, any violations of the surface water quality standards in RSA 485-A and Env-Wq 1700.

- 6. All development activities associated with this project shall be conducted in compliance with applicable requirements of RSA 483-B and N.H. Code Admin. Rules Env-Wq 1400- Shoreland Protection during and after construction.
- 7. In accordance with Env-Wt 904.02(a)(1), in-stream work shall be done only during low flow or dry conditions, in non-tidal areas.
- 8. In accordance with Env-Wt 514.05(a), materials used to emulate a natural channel bottom shall be consistent with materials identified in the reference reach. Materials should be well-mixed to adequately emulate natural boulders, cobbles, gravels and fine materials found upstream and downstream of the crossing, and to prevent the stream flow from running subsurface (i.e., within the interstitial stone voids).
- 9. American Eel (State species of special concern) and Swamp Darter (State species of special concern) occur within the vicinity of the project area. All operators and personnel working on or entering the site should be made aware of the potential presence of these species.
- 10. Turtles may be attracted to disturbed ground during nesting season (May 15th June 30th). All turtle species nests are protected by NH laws. If a nest is observed or suspected, operators shall contact Melissa Winters (603-479-1129) or Josh Megyesy (978-578-0802) at NHFG immediately for further consultation.
- 11. All manufactured erosion and sediment control products, with the exception of turf reinforcement mats, utilized for, but not limited to, slope protection, runoff diversion, slope interruption, perimeter control, inlet protection, check dams, and sediment traps shall not contain plastic, or multifilament or monofilament polypropylene netting or mesh with an opening size of greater than 1/8 inches.
- 12. All observations of threatened or endangered species on the project site shall be reported immediately to the NHFG nongame and endangered wildlife environmental review program by phone at 603-271-2461 and by email at NHFGreview@wildlife.nh.gov, with the email subject line containing the NHB DataCheck tool results letter assigned number, the project name, and the term Wildlife Species Observation.
- 13. Photographs of the observed species and nearby elements of habitat or areas of land disturbance shall be provided to NHFG in digital format at the above email address for verification, as feasible.
- 14. In the event a threatened or endangered species is observed on the project site during the term of the permit, the species shall not be disturbed, handled, or harmed in any way prior to consultation with NHFG and implementation of corrective actions recommended by NHFG.
- 15. NHFG, including its employees and authorized agents, shall have access to the property during the term of the permit.
- 16. In accordance with Env-Wt 307.05(e), to prevent the use of soil or seed stock containing nuisance or invasive species, the contractor responsible for work shall follow Best Management Practices for the Control of Invasive and Noxious Plant Species (Invasive Plant BMPs).
- 17. In accordance with Env-Wt 307.03(c)(3), water quality control measures shall be installed prior to start of work and in accordance with the manufacturer's recommended specifications or, if none, the applicable requirements of Env-Wq 1506 or Env-Wg 1508.
- 18. In accordance with Env-Wt 307.03(c)(5), water quality control measures shall be maintained so as to ensure continued effectiveness in minimizing erosion and retaining sediment on-site during and after construction.
- 19. In accordance with Env-Wt 307.03(c)(6), water quality control measures shall remain in place until all disturbed surfaces are stabilized to a condition in which soils on the site will not experience accelerated or unnatural erosion by achieving and maintaining a minimum of 85% vegetative cover using an erosion control seed mix, whether applied in a blanket or otherwise, that is certified by its manufacturer as not containing any invasive species; or placing and maintaining a minimum of 3 inches of non-erosive material such as stone.
- 20. In accordance with Env-Wt 307.03(d), any sediment collected by water quality control measures shall be removed with sufficient frequency to prevent the discharge of sediment; and placed in an upland location in a manner that prevents its erosion into a surface water or wetland.
- 21. In accordance with Env-Wt 307.03(c)(7), temporary water quality control methods shall be removed upon completion of work when compliance with Env-Wt 307.03(c)(6) is achieved.
- 22. In accordance with Env-Wt 307.03(h), equipment shall be staged and refueled outside of jurisdictional areas and in accordance with Env-Wt 307.15.

- 23. In accordance with Env-Wt 307.12(i), wetland areas where permanent impacts are not authorized shall be restored to their pre-impact conditions and elevation by replacing the removed soil and vegetation in their pre-construction location and elevation as close as practicable to pre-construction conditions.
- 24. In accordance with Env-Wt 307.12(f), if any temporary impact area that is stabilized with seeding or plantings does not have at least 75% successful establishment of wetlands vegetation after 2 growing seasons, the area shall be replanted or reseeded, as applicable.
- 25. In accordance with Env-Wt 307.12(a), within 3 days of final grading or temporary suspension of work in an area that is in or adjacent to surface waters, all exposed soil areas shall be stabilized by seeding and mulching, if during the growing season; or mulching with tackifiers on slopes less than 3:1 or netting and pinning on slopes steeper than 3:1 if not within the growing season.
- 26. In accordance with Env-Wt 307.12(f), if any temporary impact area that is stabilized with seeding or plantings does not have at least 75% successful establishment of wetlands vegetation after 2 growing seasons, the area shall be replanted or reseeded, as applicable.
- 27. In accordance with Env-Wt 307.03(g)(1), the person in charge of construction equipment shall inspect such equipment for leaking fuel, oil, and hydraulic fluid each day prior to entering surface waters or wetlands or operating in an area where such fluids could reach groundwater, surface waters, or wetlands.
- 28. In accordance with Env-Wt 307.03(g)(2), the person in charge of construction equipment shall repair any leaks prior to using the equipment in an area where such fluids could reach groundwater, surface waters, or wetlands.
- 29. In accordance with Env-Wt 307.03(g)(3) and (4), the person in charge of construction equipment shall maintain oil spill kits and diesel fuel spill kits, as applicable to the type(s) and amount(s) of oil and diesel fuel used, on site so as to be readily accessible at all times during construction; and train each equipment operator in the use of the spill kits.
- 30. In accordance with Env-Wt 307.03(e), all exposed soils and other fills shall be permanently stabilized within 3 days following final grading.
- 31. In accordance with Env-Wt 514.05(h) and Env-Wt ,307.18 (c) within 60 days of completion of construction, the applicant shall submit a post-construction report that has been prepared by a professional engineer, certified wetland scientist, or qualified professional, as applicable, and contains narrative, exhibits, and photographs, showing the extent of jurisdictional impacts, areas of restoration, and progress of any plantings shall be submitted to the department.

THIS PERMIT IS SUBJECT TO THE FOLLOWING GENERAL CONDITIONS:

- 1. Pursuant to RSA 482-A:12, a copy of this permit shall be posted in a secure manner in a prominent place at the site of the approved project.
- 2. In accordance with Env-Wt 313.01(a)(5), and as required by RSA 482-A:11, II, work shall not infringe on the property rights or unreasonably affect the value or enjoyment of property of abutting owners.
- In accordance with Env-Wt 314.01, a standard permit shall be signed by the permittee, and the principal contractor who will build or install the project prior to start of construction, and will not be valid until signed.
- 4. In accordance with Env-Wt 314.03(a), the permittee shall notify the department in writing at least one week prior to commencing any work under this permit.
- 5. In accordance with Env-Wt 314.08(a), the permittee shall file a completed notice of completion of work and certificate of compliance with the department within 10 working days of completing the work authorized by this permit.
- 6. In accordance with Env-Wt 314.06, transfer of this permit to a new owner shall require notification to, and approval of, the NHDES.
- 7. The permit holder shall ensure that work is done in a way that protects water quality per Env-Wt 307.03; protects fisheries and breeding areas per Env-Wt 307.04; protects against invasive species per Env-Wt 307.05; meets dredging activity conditions in Env-Wt 307.10; and meets filling activity conditions in Env-Wt 307.11.
- 8. This project has been screened for potential impact to known occurrences of protected species and exemplary natural communities in the immediate area. Since many areas have never been surveyed, or only cursory surveys

File # 2023-02842 April 24, 2024 Page 4 of 4

- have been performed, unidentified sensitive species or communities may be present. This permit does not absolve the permittee from due diligence in regard to state, local or federal laws regarding such communities or species. This permit does not authorize in any way the take of threatened or endangered species, as defined by RSA 212-A:2, or of any protected species or exemplary natural communities, as defined in RSA 217-A:3.
- 9. In accordance with Env-Wt 307.06(a) through (c), no activity shall jeopardize the continued existence of a threatened or endangered species, a species proposed for listing as threatened or endangered, or a designated or proposed critical habitat under the Federal Endangered Species Act, 16 U.S.C. §1531 et seq.; State Endangered Species Conservation Act, RSA 212-A; or New Hampshire Native Plant Protection Act, RSA 217-A.
- 10. In accordance with Env-Wt 307.02, and in accordance with federal requirements, all work in areas under the jurisdiction of the U.S. Army Corps of Engineers (USACE) shall comply with all conditions of the applicable state general permit.

APPROVED:

XI Part

Karl D. Benedict

Public Works Supervisor, Wetlands Bureau Land Resources Management, Water Division

THE SIGNATURES BELOW ARE REQUIRED TO VALIDATE THIS PERMIT (Env-Wt 314.01).

PERMITTEE SIGNATURE (required)

PRINCIPAL CONTRACTOR SIGNATURE (required)